



ND ELECTRICAL DEMO PLAN
1" = 30' - 0"

- DEMOLITION NOTES**
1. IN EVERY INSTANCE OF DEMOLITION AND/OR REMODELING, THE ELECTRICAL CONTRACTOR SHALL FIGURE A COMPLETE JOB AS NONE OTHER SHALL BE ACCEPTED.
 2. THE DRAWINGS ARE TO BE USED ONLY AS A GUIDELINE FOR DEMOLITION. THE ELECTRICAL CONTRACTOR MUST VISIT THE SITE PRIOR TO BIDDING TO VERIFY ALL WORK REQUIRED FOR A COMPLETE JOB & INCLUDE THE COST OF SUCH WORK IN HIS BID.
 3. THE ELECTRICAL CONTRACTOR SHALL MAINTAIN EXISTING SERVICES TO & IN THE EXISTING AREA AS REQUIRED.
 4. IF NECESSARY, THE ELECTRICAL CONTRACTOR SHALL PROVIDE TEMPORARY SERVICES IN THE EXISTING AREAS.
 5. THE ELECTRICAL CONTRACTOR SHALL DISCONNECT & REMOVE ELECTRIC SERVICE TO ALL MECHANICAL EQUIPMENT BEING REMOVED AS A RESULT OF THE REMODELING.
 6. ELECTRICAL EQUIPMENT & DEVICES SHALL BE REMOVED COMPLETE INCLUDING CONDUIT & WIRE.
 7. FLUSH MOUNTED WALL OUTLETS SHALL BE BLANKED OFF WITH A COVERPLATE. COVERPLATE COLOR SHALL BE SELECTED BY ARCHITECT.
 8. ANY EXISTING CONDUIT, WIRING AND/OR ELECTRICAL & MECHANICAL DEVICES BEING DISTURBED BY THE WORK SHALL BE REWORKED BY THIS CONTRACTOR AS REQUIRED TO RETURN TO ITS FORMER EXISTING OPERATING CONDITION.
 9. ANY CIRCUITS FEEDING THROUGH DEVICES OR EQUIPMENT BEING RELOCATED, REWORKED, OR ABANDONED & SERVING OTHER ELECTRICAL DEVICES, AND/OR EQUIPMENT SHALL BE MAINTAINED BY PROVIDING J-BOXES OR OTHER ACCEPTABLE METHOD AS REQUIRED.
 10. ALL WALLS, CEILINGS, FLOORS, ETC. BEING DISTURBED BY THE WORK SHALL BE RETURNED TO FINISHED CONDITIONS TO MATCH EXISTING BY THE ELECTRICAL CONTRACTOR & HE SHALL DO HIS OWN CUTTING & PATCHING AS NECESSARY UNDER HIS CONTRACT.
 11. EXISTING MATERIALS SHALL BE TURNED OVER TO THE OWNER. IF NOT REQUIRED BY OWNER, THE ELECTRICAL CONTRACTOR SHALL REMOVE THESE MATERIALS FROM THE PREMISES.
 12. NO CONDUIT, BOXES, WIRING, OR CABLES SHALL BE INSTALLED WITHIN 1 1/2' OF THE LOWEST POINT OF THE UNDERSIDE OF THE ROOF DECKING, NOR SHALL THEY BE INSTALLED CONCEALED WITHIN METAL-CORRUGATED ROOF DECKING. THE ELECTRICAL CONTRACTOR SHALL BE RESPONSIBLE TO REPLACE AND/OR REWORK EXISTING CONDUIT, BOXES, WIRING, AND CABLING THAT IS NOT IN COMPLIANCE WITH THIS REQUIREMENT.
 13. ALL CONDUIT AND CABLING SHALL BE PROPERLY SUPPORTED AS REQUIRED BY THE NATIONAL ELECTRICAL CODE. THE ELECTRICAL CONTRACTOR SHALL BE RESPONSIBLE TO REPLACE AND/OR REWORK EXISTING CONDUIT AND/OR CABLING THAT IS NOT IN COMPLIANCE WITH THIS REQUIREMENT.
 14. CONTRACTOR SHALL FIELD VERIFY SLAB ON GRADE FLOOR CONSTRUCTION TYPE PRIOR TO CUTTING. UNDER NO CIRCUMSTANCES SHALL THE CONTRACTOR CUT A STRUCTURAL FLOOR SLAB THICKER THAN FOUR (4) INCHES WITHOUT PRIOR WRITTEN APPROVAL FROM ENGINEER OF RECORD. NOTIFY ENGINEER OF RECORD OF ANY SLAB THICKNESS GREATER THAN FOUR (4) INCHES PRIOR TO PROCEEDING WITH ANY SAW CUTTING.

CODED NOTES:

1. EXISTING LIGHT POLE, CIRCUITING, ETC. TO BE REMOVED BACK TO SOURCE.
2. EXISTING WIRE AND CONDUIT TO BE REMOVED.
3. EXISTING FIXTURE TO REMAIN. E.C. SHALL PROVIDE NEW POWER CONNECTION TO FIXTURE. REFER TO SHEET E2.0. FIXTURE CURRENTLY FED FROM PANEL 1-2E.
4. EXISTING CONDUIT, WIRE, FIXTURE, ETC. TO REMAIN. E.C. SHALL CONDUIT AND WIRE AS REQUIRED PER REWIRE/EXTEND ANYTHING DISTURBED BY DEMO.
5. EXISTING HOMERUN TO BE REMOVED BACK TO SOURCE.
6. EXISTING UTILITY POLE TO REMAIN.

LEGEND:

DENOTES CONDUIT/WIRE TO BE DEMOLISHED.

GENERAL NOTES:

1. ALL CIRCUITS SHOWN ARE FED FROM PANEL 1-4A UNLESS OTHERWISE NOTED.

not published: all rights reserved

Thorson • Baker + Associates
CONSULTING ENGINEERS
 3030 West Streetsboro Road (330) 659-6688 Ph.
 Richfield, Ohio 44286 (330) 659-6675 Fax

STOW LIBRARY PARKING LOT
STOW-MUNROE FALLS PUBLIC LIBRARY
 3512 DARROW ROAD, STOW, OHIO

SHEET ISSUE: FOR BIDS
ISSUE DATE: 12-20-23

MARK	DATE	DESCRIPTION

PROJECT NO: 2023-0668
ORIGINAL DATE:

DEMO PLAN

E0.1

\\bs-projects\23\2023\2023-0668\TBA-Cad-Rev\MEPT\2023-0668 E0.1.dwg, 12/20/2023 1:22:20 PM